

V ADDENDUM 1

2025.07.02 D

**KEYNOTE LEGEND** 

1. EXISTING PRECAST DOUBLE TEE WALLS

2. EXISTING CONC FOUNDATION

EXISTING CONC EQUIPMENT PAD

EXISTING CONC COLUMN/PIER

EXISTING 6" SLAB TO REMAIN

6. EXISTING BRICK VENEER WALL

DEMO EXISTING SLAB AS REQUIRED TO INSTALL NEW SHALLOW FOUNDATIONS AND PILE CAPS FOR PIPE RACK.

EXIST 4'-0" X 4'-0" X 1'-0" ISOLATED FOUNDATION TO BE DEMOLISHED

EXISTING 1'-6" X 1'-6" CONC PIER TO BE

DEMOLISHED 10. EXISTING 1'-2" X 2'-0" GRADE BEAM TO BE

DEMOLISHED

11. EXISTING 6" CONC SLAB TO BE DEMOLISHED TO INSTALL NEW FOUNDATIONS

12. EXISTING 1'-4"W X 5'-0"H RING FOUNDATION TO BE DEMOLISHED

13. EXISTING CONC WALL AND VAULT TO BE DEMOLISHED.

## **GENERAL NOTES**

REFER TO SHEET S0.01 THROUGH S0.04 FOR GENERAL NOTES AND STRUCTURAL **SPECIFICATIONS** 

CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND COORDINATE W/ EXISTING CONDITIONS. STRUCTURAL ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCIES.

ALL STRUCTURAL STEEL INCLUDING FRAMING MEMBERS, CONNECTION MEMBERS, HARDWARE, BASE PLATES, AND ANCHOR BOLTS TO BE HOT DIP GALVANIZED.

CONTRACTOR SHALL COORDINATE DIMENSIONS W/ MECHANICAL DRAWINGS AND EXISTING CONDITIONS. STRUCTURAL ENGINEER SHALL BE NOTIFIED OF ANY DISCREPANCIES.

## STRUCTURAL ELEVATIONS

T/EXIST FDN EL 101'-6", FV

T/SLAB 106'-0", FV

T/GRADE BEAM EL 103'-6", FV T/EXIST PIER EL 106'-0", FV

Title: AMALGAMATED SUGAR COMPANY EVAPORATOR PROJECT FOUNDATION AND SLAB DEMOLITION PLAN



2 JULY 2025

Ph: 239.768.1778, Fax: 239.210.2168

http://www.veiglobal.com

AMALGAMATED SUGAR COMPANY 2320 ORCHARD DRIVE EAST TWIN FALLS, ID 83301

Date: 07/01/2025 Chkd By: <u>S.WILSON</u> Dsgn By: <u>D.VIELE</u> E24140

SD1.01 C:\Users\dviele\Documents\E24140 ASC Evaportator STR R25 backup\_dviele@veiglobal.com.rvt